

Queries & Clarifications Furnished-1

Date: 14.11.2011

Consultancy Services for the Preparation of Detailed Project Report for Improvements to Thiruvottiyur – Ponneri – Panchetti (TPP) Road, North Chennai Thermal Power Station (NCTPS) Road, and Ennore Port Road for Movement of 575MT Special Transport vehicle (STV) – in Chennai, Tamil Nadu

S No	Query Raised	Response / Clarification
1	The objective of the consultancy is to design various components as listed in TOR. We suggest that in case of Napallayam Bridge, Athipettu ROB and Pulicat Backwater Bridge, only 4nos. of deep bore holes for each bridge can be done instead of at all pier locations. 4 nos. will cover 2 abutments and 2 internal locations which is sufficient for design purpose. This will save time and cost of consultancy. Confirmatory bore at each pier location may be done by the contractor at the time of actual execution. PI confirm.	Refer to S.No 3 of the Pre-bid queries and clarifications furnished. The minimum scope of Geo-Technical investigations shall be as specified in the ToR.
2	In case of Napallayam Bridge, all piles as per the existing design had been completed and pier caps done. At some locations, columns and columns with Pier caps have been completed. Hence Non Destructive Tests called for in the Tender can cover Testing of Concrete Strengths in various components only. PI confirm.	Refer to S.No 3 of the Pre-bid queries and clarifications furnished. The NDT Assessment shall be carried out on the existing components.
3	Environmental studies will be done to the need of Pollution Control board of TN. PI confirm	Environmental and Social Impact Assessment as shall be in accordance with the ToR.