

“Improvement to Roads, Bridges and Culverts of North Chennai Thermal Power Station Road and Ennore Port Road for the Movement of 575 MT Special Transport Vehicle in Thiruvallur District, Tamil Nadu ”

Pre – Bid Meeting held on **February 18th , 2013 (at 15:00 hrs)**, Venue- Conference Hall, TNRDC, Sindhur Panthion Plaza, 2nd Floor, 346, Pantheon Road, Egmore,

RESPONSE TO PRE BID QUERIES

Package - I- Improvement, strengthening, widening and realignment of NCTPS Road including construction of bridges and culverts but excluding RoB at Athipattu (Km 0/00 to Km 4/800)

| S No | Queries Raised | Response to Queries by the Employer |
|-------------|---|---|
| 1 | We request you to provide Land for erection of Concrete plant. | Land will not be provided by TNRDC |
| 2 | We request you to provide Interest free mobilization advance against Bank guarantee. | As per Clause 47.1 of GCC part of the Bid Document "No Mobilisation advance/Machinery and equipment advance payment will be made to the Contractor for the works" |
| 3 | Can we use equivalent cementitious material like cement or lime instead of RBI Grade 81. | The Bidder shall follow the specifications given in the Bill of Quantities |
| 4 | For Item: 2 . Structures major bridge: Kindly provide loading details for Pile load test | *Design Load of 300 MT/ as mentioned in pile layout drawing |
| 5 | Item:5.02 . Drainage & Protective works: Kindly provide drawing for energy dissipation basin | *Drawings will be provided in Addendum -I |
| 6 | For Item: 5.06 . Drainage & Protective works: Kindly provide drawing for lined trapezoidal drain & kindly mention the thickness of stone pitching | *Drawings will be provided in Addendum -I |

| S No | Queries Raised | Response to Queries by the Employer |
|------|--|---|
| 7 | For Item: 6.07-Road Furniture : Kindly provide drawing for guard stone | The Bidder shall follow the MORTH standard drawings |
| 8 | For Item: 14 . Structures major bridge: Kindly clarify the mastic asphalt 6mm thick included in | Yes. |
| 9 | For Item: 14&15 . Structures major bridge: Kindly clarify the mastic asphalt shall be provided for the both item | Yes. |
| 10 | For Item: 16 . Structures major bridge: Kindly provide drawing for ms railing | *Drawings will be provided in Addendum -I |
| 11 | For Item: 18 . Structures major bridge-Perforated 150mm dia PVC pipe - Kindly provide the location where it will be used | Only Non Perforated PVC Pipes shall be used at Desk Slab |
| 12 | For Item: 8 & 9 . Box/Slab Culverts-- Kindly provide thickness of floor & Flexible aprons | 300MM R.R. should be used in flexible aprons |
| 13 | As per section I ,clause 12.3 kindly clarify whether service tax is applicable | The rates quoted by the bidder will be considered to be inclusive of all applicable taxes from time ot time |
| 14 | Kindly clarify whether estimate is made based on SOR 2012-2013 | Yes |

Package - II- Improvement, strengthening, widening, realignment of Ennore Port Road including construction of bridges and culverts. (Km 0/00 to Km 2/400)

| S No | Queries Raised | Response to Queries by the Employer |
|------|---|--|
| 1 | We request you to provide Land for erection of Concrete plant. | Land will not be provided by TNRDC. |
| 2 | We request you to provide Interest free mobilization advance against Bank guarantee. | As per Clause 47.1 of GCC part of the Bid Document "No Mobilisation advance/Machinery and equipment advance payment will be made to the Contractor for the works". |
| 3 | For Item: 2 . Structures minor bridge: Kindly provide loading details for Pile load test | *Design Load of 300 MT /as mentioned in pile layout drawing. |
| 4 | For Item:5.02 . Drainage & Protective works: Kindly provide drawing for energy dissipation basin | *Drawings will be provided in Addendum -I |
| 5 | For Item: 5.05 . Drainage & Protective works: Kindly provide drawing for lined trapezoidal drain & kindly mention the thickness of stone pitching | *Drawings will be provided in Addendum -I |
| 6 | For Item: 6.07-Road Furniture : Kindly provide drawing for guard stone | The Bidder shall follow the MORTH standard drawings |
| 7 | For Item: 13&14 . Structures minor bridge: Kindly clarify the mastic asphalt shall be provided for the both item | Yes. |

| S No | Queries Raised | Response to Queries by the Employer |
|---|---|--|
| 8 | For Item: 15 . Structures minor bridge: Kindly provide drawing for ms railing | *Drawings will be provided in Addendum -I |
| 9 | For Item: 17 . Structures minor bridge- Perforated 150mm dia PVC pipe - Kindly provide the location where it will be used | Only Non Perforated PVC Pipes shall be used |
| 10 | For Item: 3. 9a. Culverts- kindly confirm that the unit considered is tonneq | Shall be read as the Amended Specifiacion in Addendum -I |
| 11 | For Item: 8 & 9 . 9a. Culverts - Kindly provide thickness of floor & flexible aprons | 300MM R.R. should be used in flexible aprons |
| 12 | As per section I ,clause 12.3 kindly clarify whether service tax is applicable | The rates quoted by the bidderwill be considered to be inclusive of all applicable taxes from time ot time |
| 13 | Kindly clarify whether estimate is made based on SOR 2012-2013 | Yes. |
| <i>*Drawings are provided in Addendum - I for clarity.</i> | | |